



Quote: 1ES10OCT24

To: City of Deer Park (Buy Board 757-24)

Attention: Tiffany

Project: East Meadow Park - Black Vinyl Chain Link & Ornamental Iron Fence -Rev 1

Date: 2/12/2025

Foster Fence will provide the following:

-Install 480 linear feet of 6' black vinyl chain link fence w/2" x 8ga fabric (extruded), 1 5/8" schedule 40 top rail, 2 3/8" schedule 40 line post spaced 10' on center, 3" schedule 40 terminal post and brace/truss at ends, pulls, corners, and gates.

-Fence frame work will be powder coated black.

-Install 480 linear feet of 6' pvc bottom locking slats. (Black)

-Demo 58 linear feet of existing 6' iron fence and haul off site.

-Demo 350 linear feet of existing 3' iron fence and haul off site.

Install 334 linear feet of 3' ornamental iron fence w/3/4" flat top pickets spaced 6" on center, 1 1/2" top and bottom rails bracketed to 2 1/2" square post spaced 8' on center. (Iron fence close match to existing)

-Install (1) 16' wide ornamental iron double swing gate w/post and standard hardware.

-Excludes clearing old post holes along fence line.

-Excludes grading and leveling dirt prior to new fence install.

-Excludes 911 provisions, permits, electrical, access controls, mow band, and fence grounding.

-Mobilization to and from the job site, supervision, and management required for complete installation.

Total - \$58,826.00* - Tax not included

Estimated Taxes (if applicable) - \$0.00

***Quotes are good for 30 days**

Estimator: Elbert Salas - 713-851-1098 - esalas@fosterfence.com

Members of: Avetta, ISNetworld, Houston Area Safety Council and C3 Accredited

Exclusions - unless specifically included in quote:

(281) 456-7273
(281) 456-0221 Fax

FOSTER FENCE LTD
P.O. BOX 96116

www.fosterfence.com
info@fosterfence.com



Houston, TX 77213

- * Demolition, clearing & grubbing, spoil removal
- * Electrical work, access controls, and conduits
- * Fence and controls grounding.
- * Engineered drawings.
- * Fence or fire department permitting.
- * Property surveying and site layout. The final location of the fence installation is to be verified with the customer/agent and Foster Fence staff before starting the installation.
- * Tree protection, silt fence, temporary fence.
- * Hand digging, hydro-excavation, core drilling, rock drilling, probing.
- * Concrete & asphalt breaks.
- * Signage, bollards, concrete mow strip.
- * Painting, staining, galvanizing after fabrication.
- * Utility locates beyond 811 One call, location of water lines. Private utility lines are not covered by 811. Locating private lines is the responsibility of the property owner.
- * OQ training, OSHA 30 Training, site or hazard specific training greater than 30 minutes
- * Remobilizations, down time, standby time.
- * OCIP, CCIP, Builders Risk, Payment and Performance Bonds

Commerical Conditions

- * All projects requiring special fabrication as well as contracts with a value greater than \$75,000 will require signed and approved submittals before Foster Fence, Ltd. proceeds with construction.
- * Lead times are projected after submittals are approved.
- * Terms - Net 30, unless otherwise expressly negotiated
- * All standy/down time in excess of 30 minutes will be billed at a rate of \$400 per hour.
- * Restocking fee for standard stock materials 25%, non-stock materials 100%
- * Foster Fence Ltd. agrees to guarantee all materials to be free from defects in materials and workmanship for a period of one year from installation. This guarantee does not cover abuse, Acts of God, Nature, or other external source.

CUSTOMER SIGNATURE

DATE
