

CITY OF DEEER PARK

Change Order No. 1

12" South Plant LS Force Main Rehabilitation 5/5/2016

Brief Description of Changes:

This CO will add additional line items to the project in order to repair the 8" gravity sewer that is below the existing FM. During construction it was found that the existing pipe was made of clay and in poor condition. Continuing with the Force Main rehabilitation will cause the clay gravity line to collapse.

Add or Delete Items:

Item	Description	Unit	Quantity	Unit Price	Total
16100	Pipe burst 8" to 8" HDPE SDR 19	LF	833	40.00	\$ 33,320.00
16112	Pipeburst setup charge	LF	833	1.00	\$ 833.00
19101	8" Clean and TV sanitary sewer	LF	833	4.00	\$ 3,332.00
19130	** post TV inspection	LF	833	2.00	\$ 1,666.00
20109	External service reconnect	EA	12	565.00	\$ 6,780.00
29131	Sanitary sewer cleaout	EA	12	325.00	\$ 3,900.00
					\$ -
Total					\$ 49,831.00

Contract Summary:

Original Contract Price	\$ 821,255.04
Previous Change Orders	\$ -
This Change Order	\$ 49,831.00
Revised Contract Price	\$ 871,086.04
Original Contract Duration - Calendar Days	120
Previous Time Extensions	
This Change Order	
Revised Contract Duration - Calendar Days	120

Contractor Date

Director of Engineering Date