



Quote Number: 1ES23MAY25

To: City of Deer Park (Buy Board 757-24)

Attention: Kathy / Matt

Project: Water Facilities Fence Replacement - Rev 2

Date: 23-May-2025

Foster Fence will provide and install the following:

East P St. - \$50,203.00

- Install 706 LF of 8' fence.
- Install (1) 20' wide galvanized chain link cantilever sliding gate w/post and standard hardware.

East Ave L - \$42,477.00 (Pasadena Blvd.)

- Install 650 LF of 8' fence.
- Install (1) 17' wide galvanized chain link double swing gates w/post and standard hardware.

Coy Dr. - \$44,949.00

- Install 657 LF of 8' fence.
- Install (1) 12' wide galvanized chain link double swing gates w/post and standard hardware.
- Install (1) 16' wide galvanized chain link double swing gates w/post and standard hardware.
- Includes demo and haul off existing fence.
- Maintain security throughout fence replacement.
- Post on concrete will be anchor bolted to concrete.
- No written fence specifications or detailed drawing were provided.
- Excludes 911 provisions, permits, electrical, access controls, mow band and fence grounding.
- Mobilization to and from the job site, supervision, and management required for complete installation.



Total \$137,629.00 Tax not included

Estimated Taxes \$0.00 *If applicable

*Quote is good for 30 days

Elbert Salas - esalas@fosterfence.com - 713-851-1098

*Lead times are projected after submittals are approved



Standard Exclusions- unless specifically included in the quote:

- Work to be performed during standard business hours, 7am-5pm Monday through Friday. Any work that needs to be performed after hours or on the weekend will come at an added cost and will need to be quoted accordingly.
- Demolition, clearing & grubbing, spoil removal.
- Electrical work, access controls, and conduits.
- Fence and controls grounding.
- Engineered drawings and Building Information Modeling (BIM).
- Fence of fire department permitting.
- Property surveying and site layout. The final location of the fence installation is to be verified with the customer/agent and Foster Fence staff before starting the installation.
- Tree protection, silt fence, temporary fence.
- Hand digging, hydro-excavation, core drilling, rock drilling, and probing.
- Concrete & asphalt breaks.
- Signage, bollards, concrete mow strip.
- Painting, staining and galvanizing after fabrication.
- Utility locates beyond 811 One call, location of water lines. Private utility lines are not covered by 811. Locating private lines is the responsibility of the property owner.
- OQ training, OSHA 30 Training, site, or hazard-specific training greater than 30 minutes.
- Re-mobilizations, downtime, standby time.
- OCIP, CCIP, Builders Risk, Payment, and Performance Bonds.

Commercial Conditions:

- All projects requiring special fabrication as well as contracts with a value greater than \$75,000 will require signed and approved submittals before Foster Fence, Ltd. proceeds with construction.
- Lead times are projected after submittals are approved.
- Terms – Net 30, unless otherwise expressly negotiated.
- All standby/downtime of more than 30 minutes will be billed at a rate of \$400 per hour.
- Restocking fee for standard stock materials 25%, non-stock materials 100%.
- Foster Fence Ltd. agrees to guarantee all materials are free from defects in materials and workmanship. for a period of one year from installation. This guarantee does not cover abuse, Acts of God, nature, or other external sources.

Customer Signature

Date