



**Quote:** 4ES30APR25

**To:** City of Deer Park (Buy Board 757-24)

**Attention:** Tiffany

**Project:** Deer Park Adult Softball Fields - Pasadena Blvd - Field 1 Outfield & Foul Lines

**Date:** 4/30/2025

**Foster Fence will provide the following:**

**Field 1 Outfield, Right, & Left Field Fences**

- Demo 1,024 linear feet of 6' galvanized chain link fence.
- Demo (1) 12' wide double swing gate.
- Install 1,024 linear feet of 6' galvanized chain link fence w/2" x 9ga fabric (1.2oz), 1 5/8" schedule 40 top, middle, and bottom rail, 2 3/8" schedule 40 line post spaced 10' on center, and 3" schedule 40 terminal post.
- Install (1) 12' wide galvanized chain link double swing gate w/post and standard hardware.
- Install (2) 4" x 10' tall yellow foul poles.
- Excludes 911 provisions, permits, electrical, access controls, mow band and fence grounding.
- Mobilization to and from the job site, supervision, and management required for complete installation.

**\*Lead times are projected after submittals are approved**

Total - \$62,122.00\* - Tax not included

Estimated Taxes (if applicable) - \$0.00

**\*Quotes are good for 30 days**

**Estimator: Elbert Salas - 713-851-1098 - [esalas@fosterfence.com](mailto:esalas@fosterfence.com)**

**Members of: Avetta, ISNetworld, Houston Area Safety Council and C3 Accredited**

**Exclusions - unless specifically included in quote:**

---

(281) 456-7273  
(281) 456-0221 Fax

FOSTER FENCE LTD  
P.O. BOX 96116  
Houston, TX 77213

[www.fosterfence.com](http://www.fosterfence.com)  
[info@fosterfence.com](mailto:info@fosterfence.com)



- \* Work to be performed during standard business hours, 7am-5pm Monday through Friday. Any work that needs to be performed after hours or on the weekend will come at an added cost and will need to be quoted accordingly.
- \* Demolition, clearing & grubbing, spoil removal
- \* Electrical work, access controls, and conduits
- \* Fence and controls grounding.
- \* Engineered drawings and Building Information Modeling (BIM)
- \* Fence or fire department permitting.
- \* Property surveying and site layout. The final location of the fence installation is to be verified with the customer/agent and Foster Fence staff before starting the installation.
- \* Tree protection, silt fence, temporary fence.
- \* Hand digging, hydro-excavation, core drilling, rock drilling, probing.
- \* Concrete & asphalt breaks.
- \* Signage, bollards, concrete mow strip.
- \* Painting, staining, galvanizing after fabrication.
- \* Utility locates beyond 811 One call, location of water lines. Private utility lines are not covered by 811. Locating private lines is the responsibility of the property owner.
- \* OQ training, OSHA 30 Training, site or hazard specific training greater than 30 minutes
- \* Remobilizations, down time, standby time.
- \* OCIP, CCIP, Builders Risk, Payment and Performance Bonds

#### **Commercial Conditions**

- \* All projects requiring special fabrication as well as contracts with a value greater than \$75,000 will require signed and approved submittals before Foster Fence, Ltd. proceeds with construction.
- \* Lead times are projected after submittals are approved.
- \* Terms - Net 30, unless otherwise expressly negotiated
- \* All standby/down time in excess of 30 minutes will be billed at a rate of \$400 per hour.
- \* Restocking fee for standard stock materials 25%, non-stock materials 100%
- \* Foster Fence Ltd. agrees to guarantee all materials to be free from defects in materials and workmanship for a period of one year from installation. This guarantee does not cover abuse, Acts of God, Nature, or other external source.

**CUSTOMER SIGNATURE**

**DATE**

---

---