

CITY OF DEER PARK

Change Order No. 1

Year 6 SSO Program
1/18/2017

Brief Description of Changes:

This Change Order is for additional footage of 8" and 12" concrete pipe that was found during construction to be in poor condition with delaminated liner that was installed in 2001. This liner has collapsed in sections of the pipe blocking flow. The liner will be removed and the pipe rehabilitated with new HDPE pipe.

Add or Delete Items:


Item	Description	Unit	Quantity	Unit Price	Total
CO1	See attached unit price breakdown	UP	1	74,132.51	\$ 74,132.51
Total					\$ 74,132.51

Contract Summary:

Original Contract Price	\$ 710,983.86
Previous Change Orders	\$ -
This Change Order	\$ 74,132.51
Revised Contract Price	\$ 785,116.37
Original Contract Duration - Calendar Days	180
Previous Time Extensions	
This Change Order	
Revised Contract Duration - Calendar Days	180

Contractor _____ Date _____

Assistant Director of Engineering _____ Date _____



FUQUAY, INC.

P. O. Box 310946, New Braunfels, TX 78131



Phone (830) 606-1882 Fax (830) 606-1885

FUQUAY, INC.

Name of Project: Pipe Burst SSO Year 6 Project

CHANGE ORDER 1

Date: December 31, 2016

Item	Description	Unit	Original QTY	C.O. QTY	FINAL QTY	Unit Price	Change Order Amount
16100	Burst existing 6" or 8" to 8" IPS SDR 19 (0'-8' deep)	LF	10950	607	11557	37.00	22,459.00
17112	New manhole frame and cover, incld. WW Access Chamber	EA	11	-3	8	1,700.00	-5,100.00
20109	External reconnect (0'-8' deep)	EA	270	-19	251	440.00	-8,360.00
20111	Extra length service over 5' long	LF	150	-133	17	25.00	-3,325.00
29366	Remove Miscellaneous Concrete	SF	225	-125.01	99.99	5.00	-625.05
29368	Hot Mix Asphaltic Pavement - Type D (2" Compacted Depth)	SY	40	-40	0	49.00	-1,960.00
29369	Repair/Rehab 10" Flex base	SY	40	-40	0	40.00	-1,600.00
29375	Portland Cement Concrete Driveway, 6" thickness	SY	25	-13.89	11.11	80.00	-1,111.20
17116	Manhole Rehabilitation - Cementitious (CRM) only -- 1 inch thickness	SF	3166	-3166	0	8.00	-25,328.00
16104	Burst existing 10" or 12" to 12" IPS SDR 19 (0'-8' deep)	LF	0	366	366	70.00	25,620.00
20112	Access Pit (0'-8' deep)	EA	0	2	2	2,980.00	5,960.00
20114	Potholing for Nearby Utility Location (0'-8' deep)	EA	0	2	2	695.00	1,390.00
29157	RC PIPE (CL III)(24 IN)	LF	0	100	100	69.00	6,900.00
29171	Trench Safety- Stormwater	LF	0	20	20	2.50	50.00
29365	Remove Sidewalks & Driveways	SF	0	160	160	2.60	416.00
29376	Portland Cement Concrete Driveway - Commercial, 8" thickness	SY	0	18	18	90.00	1,620.00
29412	Travel and Mobilization- Excavator or Backhoe Crew from New Braunfels, TX	MILE	0	194	194	20.00	3,880.00
20124	Excavation, Dirt	CY	0	68.08	68.08	79.50	5,412.36
20127	Travel and Mobilization- Excavator or Backhoe Crew from New Braunfels, TX	MILE	0	194	194	21.80	4,229.20
26119	St. Augustine Sodding	SY	0	300	300	20.00	6,000.00
29364	Remove Concrete Curb	LF	0	78	78	7.90	616.20
29366	Remove Miscellaneous Concrete	SF	0	534	534	5.10	2,723.40
29368	Hot Mix Asphaltic Pavement - Type D (2" Compacted Depth)	SY	0	238	238	49.75	11,840.50
29369	Repair/Rehab 10" Flex base	SY	0	238	238	39.95	9,508.10
29372	Concrete Curb, Gutter, and Concrete Curb and Gutter	LF	0	78	78	29.75	2,320.50
29375	Portland Cement Concrete Driveway, 6" thickness	SY	0	42	42	79.50	3,339.00
29403	Backhoe and Operator (4 hour minimum)	HR	0	35	35	84.50	2,957.50
29122	Sanitary Sewer Manhole, 48" Diameter (0'-6')	EA	0	1	1	3,510.00	3,510.00
17112	New manhole frame and cover	EA	0	1	1	790.00	790.00

\$74,132.51