



# **DEER PARK FIRE STATION #3**

## **PYLON SIGN**

**2211 East X St.  
Deer Park, TX 77536**



**National Signs**  
CREATING LANDMARKS TOGETHER.

**SCOPE OF WORK:**  
FABRICATE & INSTALL DOUBLE FACED ILLUMINATED PYLON WITH LED DISPLAY

**ALL ALUMINUM CONSTRUCTION:**

- ARCHED CABINET: FINISH: P1 AND P2
- TEXT: ROUTED INTO FACE AND BACKED WITH 3/16" THICK, #7328 WHITE ACRYLIC, WITH 1ST SURFACE APPLIED, V1 VINYL
- SUPPORT PIPES: 3 ½"Ø STANDARD STEEL PIPE W/4" O.D. X .226 THICK WALL FINISH: P2

**MAIN ID & SECONDARY ID CABINET:** FINISH: P3

- TEXT: ROUTED INTO FACE AND BACKED WITH ¾" THICK CLEAR ACRYLIC, 3/8" TO EXTEND PAST FACE -- 2nd SURFACE VINYL DIFFUSER APPLIED AND 1ST SURFACE V3 APPLIED WHITE VINYL

**FLAT CUT OUT STAR:** .125 ALUMINUM FLUSH MOUNTED TO CABINET FACES  
FINISH: P3 WITH APPLIED V2 VINYL

**REVEALS:** 2" HIGH, FINISH: P2

**LED DISPLAYS:**

- 108 X 216 FULL COLOR LED MATRIX (10mm PIXEL PITCH)
- 4'-0" HIGH 7'-7" WIDE DISPLAY AREA
- 3'-7" HIGH 7'-3" WIDE CABINET
- FULLY PROGRAMMABLE TEXT & GRAPHICS
- COMMUNICATIONS: ETHERNET BRIDGE RADIO REQUIRED ONLY IF DISTANCE BETWEEN ETHERNET ROUTER AND LED DISPLAY IS OVER 250 FEET
- OPEN LINE OF SIGN FROM TRANSMITTER TO SIGN REQUIRED
- TEMPERATURE SENSOR IS NOT INCLUDED
- FILLER BETWEEN CABINETS: FINISH: P2

**POLE COVER:** FINISH: P2 AND P4  
**ACCENTS ON POLE COVER:** FINISH: P5







**CONCRETE PAD:** 3" LARGER ALL AROUND THAN SECTION ABOVE. MIN 4" ABOVE GRADE/ MIN 3" BELOW GRADE

**SUPPORT & FOUNDATION AS PER ENGINEERING REQUIREMENTS**




- INTERNALLY ILLUMINATED
- ALUMINUM ANGLE FRAME
- NO VISIBLE FASTENERS ON FACE
- COUNTER SUNK SCREWS ON ENDS

**FINISH SCHEDULE**


PAINT COLORS - SATIN FINISH

	P1: PMS WARM GRAY 8C
	P2: MP BLACK
	P3: PTM DK BURGUNDY 220-68
	P4: PMS 504C BROWN
	P5: PMS 7407C GOLD
	P6: MP WHITE

VINYL COLORS

	V1: TRANS. GOLD NUGGET 230-131
	V2: DTM GOLD PMS 7407C & BROWN PMS 504C (WITH PROTECTIVE LAMINATE)
	V3: TRANS. WHITE 230-20

APPROVED BY: \_\_\_\_\_



SIGN DETAIL

SCALE: 3/8" = 1'-0"



EXISTING CONDITION



UPDATED CONDITION

SIGN ELEVATION

SCALE: 3/16"=1'-0"